12. The deposit of Rs. 200 will remain as security for the due fulfilment of all and every one of the terms of sale for the breach of any of which by the purchaser, the District Forest Officer shall be entitled to forfeit the deposit in whole or in part and in the event of such forfeiture, the sum so forfeited shall be immediately made good by the purchaser so long as the transaction is not finally closed. The security deposit or the balance thereof, if any, shall be returned to the purchaser after the full value of timber purchased has been paid for and the timber fully removed.

M. MACHIYA,
District Forest Officer.

ENGINEERING DEPARTMENT.

SHIMOGA DIVISION.

Dated 30th November 1925.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 21st December 1925 for restoring the Kuskur-Herikere Tank R. No. 1038 of Shikarpur Taluk, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for restoring the Kuskur-Herikere Tank R. No. 1038 of Shikarpur Taluk, Shimoga District, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for Restoring the Kuskur Tank Registered No. 1038 of Shikarpur Taluk, Shimoga District :—

Items of work	Per	Quantity
1. BUND AT R. L. 55·00 TOP WIDTH 6' THROUGHOUT.		
Clearing rubbish, scraping grass and picking the top of bund for the seat of embankment.	Lump sum	
Earth work to bund including watering and tamping, etc., complete	C.yd.	15,182
Turfing the front and rear slopes of the bund	S.yds.	11,921
Providing grade stones with bed slabs including figuring, painting and fixing, etc., complete.	Each	21
Providing index stones with bed slabs including figuring, painting and fixing, etc., complete.	,,	21
Providing date stone with bed slabs including figuring, painting and fixing, etc., complete	,,	1
Providing Registered No stone with bed slabs including figuring, painting and fixing, etc., complete	,,	1
Providing bench mark stones	,,	2
Providing gauge stone 12' high	,,	1
2. SLUICE EXISTING.		
Examining the sluice after cutting open the bund and repairing the damaged portion.	Lump sum	
3. WASTE WEIR, 30 FEET LONG AT R. L. 50·00 AT LEFT FLANK.		
Earthwork excavation for body wall, etc.	C.yd.	61
Burnt brick-in-surki mortar	C.ft.	426
Burnt stone slabs dressed 6" thick	S.ft.	114
Painting with cement to joints of slabs	Sq.	2
Plastering with surki mortar	,,	3·75
Rough stone work, new, with jelly backing	C.yd.	59
Clearing draft channel to the right waste weir	Lump sum	
Double dove tailed pin joints for the covering slabs of body and toe wall ..	,,	

Dated 10th November 1925.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Shimoga Division, up to 21st December 1925, for restoring Maravanji-Doddakere Tank R. No. 280. Channagiri Taluk, Shimoga District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Maravanji-Doddakere Tank R. No. 280 of Channagiri Taluk, Shimoga District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for restoring Maravanji-Doddakere Tank Registered No. 280 of Channagiri Taluk, Shimoga District :—

No.	Items of work	Per	Quantity
	BUND AT R. L. 56·00 TOP WIDTH 0' AT BREACHES AND 6' AT REMAINING PLACES.		
1	Jungle clearing and removing roots throughout the bund	Lump sum	..
2	Scraping grass, removing silt, picking and cutting trenches wherever necessary, to receive the new earthwork.	do	..
3	Earthwork to bund including consolidation	C.yds.	6,040
4	Earthwork cutting the existing bund for building up the puddle wall and refilling the same with steps and grips as shown in longl. section of bund.	,,	1,840
5	Removing silt and cutting trenches etc , at the two breach sides	Lump sum	..
6	Turfing front and rear slopes	S.yds.	1,510
7	Gravel backing for revetment at breaches including average lead of half a mile	C.yds.	171
8	Puddle wall at centre of breaches as per details	,,	1,454
9	Revetment rough stone work, new	,,	510
10	Grade stones including dressing, numbering, painting and fixing, complete	Each	15
11	Index stones	,,	15
12	Gauge stones	,,	1
13	Inscription stone including survey and constructive details	,,	1
14	B. M. stones	,,	2
	RIGHT WASTE WEIR AT R. L. 50·00 OF 75'.		
15	Earthwork excavation	C.yds.	22
16	Burnt brick in surki mortar	C.ft.	341
17	Burnt stone slabs dressed 6" thick	S.ft.	136
18	Plastering with mortar	Lump sum	..
19	Double dove detailed pin joints or jogle joints for the coping slabs of body wall	Each	14
20	Revetment rough stone work, new	C.yds.	33
21	Draft clearing excavation	,,	1,631
	LEFT WASTE WEIR R. L. 50·00 OF 100'.		
22	Earthwork excavation	C.yds.	20
23	Burnt brick in surki mortar	C.ft.	358
24	6" to 4" burnt stone slabs	S.ft.	168
25	Plastering with surki mortar to the front of steps and return and providing stone revetment at the dismantled portion of the existing revetment for building up the return into the bund.	Lump sum	..
26	Double dove tailed pin or jogle joints for the coping slabs	Each	19
27	Draft clearing (excavation)	C.yds.	774

N. ANANDALWAR *Executive Engineer.*

G B